Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
KSRB 7.10 : Providing and fixing in position anodized aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 101.65x31.75mm. with 1.2mm thick, bottom section weight 0.695 kg/rn, sides and top sections 1.3 mm. thick weight 0.659 kg/rn; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg./m; shutter inner side 40mmx18mm, 1.25mm.thick weight 0.417 kg/rn, shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469 kg/rn. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc., glass for shutters fitted with rubber beading alums mitred subdividing the frame tenonned and rivetted in the assembled frame stiffened with end clips at corners angles etc., and t per specifications. Specification No. KBS P-32-33/I.7.10.1PW, P & WTD SOUTH ZONE -SR 2016-	Sqm							
SF-W		10	1.50		1.20	18.00		
		10	1.50		0.45	6.75		
						24.75	4123.44	**102055.00**
Basic Rate	3818.00							
Add Area Weightage 8%	305.44							
Total	4123.44							
KSRB 7.14 : Providing, fabricating, assembling and fixing in position anodized aluminium partitions using sections in combination of plain, single grove and double grove as per requirements for the frames of overall size 101.6mm x 44.45mm, 3.18mm.thick having section weight, plain sections 2.40kg/m single grove section 2.541kg/rn. and double grove section 2.683 kg/m and bottom member 114.3mmx44.45mm 3.18mm thick weight 2.646 kg/rn; aluminium louvres of size 77.8mmx27.6rnm 1.7mm. thick section weight 0.483kg/rn; bottom portions provided with 12mm. thick laminated sheet both side of approved colour lamination exterior grade; aluminium sections of mat finish or glossy finish using section, spacing of vertical member shall not exceed 0.6 m. c to c sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and rivetted to the frames,	Sqm							

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
	the assembled frame should be stiffened with corner angles stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns or rnasonry on sides, R.C.C. lintels or bearns at top and floor at bottom, including cutting chistling and making good with cement mortar to match the surface, providing and fixing bottom panel filled with the materials to a height of 0.9rn. from floor level; and 5.5mms; vertical members embedded in the flooring by making suitable size holes and fixing with cement mortar, with necessary opening for fixing of doors of standard size (excluding cost of door opening) All the frame should be throughly cleaned free from rust, scale or dirt including cost of materials, fixtures, labour and HOM of machinery complete as per specifications. (P.34-35/I.7.14.1PW, P. & IWTD -SR-2016-17)								
			1	4.50		2.10	9.45		
	Deduction -D		1	1.10		2.10	2.31		
							7.14	5030.64	**35919.00**
	Basic Rate	4658.00							
	Area Weightage 8%	372.64							
	Total	**5030.64**							
	KSRB 7.16 Providing, fabricating, assembling and fixing in position anodized aluminium shutters to the existing door frame in the partition using 47.62x44.45mm section thickness 3.18mm, weight 1.505kg/rn for vertical frame; 47.62x44.45 thickness of 3mm, weight 1.42kg/rn for top section, 48.91 mmx44.45mm with wall thickness 3mm, weight 1.495kg/rn for central rail; and 11 4.3mmx44.45mm thickness 3.18mm, weight 2.646kg/rn for bottom rail using aluminium sections anodized 12 to 15 microns and cut to length joint metred and corners grinded, the bottom rail and top rail hinged or pivoted, opening arrangements including providing and fixing standard approved accessories, such as aluminium handles, tower bolts, lock, pivots: hinges P.V.C. or rubber gasket, 12mm prelaminated sheets (Novopan) exterior grade of approved colour both sides same colour for bottom panel of maximum height 0.90rn and 5.5mm thick plain glass for top	Sqm							

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
	19mmx17.3mmx11 mm, 0.9mm thick, weight 0.124kg/rn; aluminium sections treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non-adherance of mortars or any other sticky materials, including cost of materials, fixtures, labour and HOM of machinery complete as per specifications. (P.36/I.7.16.1 PW, P & IWTD, SOUTH ZONE -SR-2016-17)								
	D		1	1.10		2.10	**2.31**	4290.84	**9912.00**
	Basic Rate	3973.00							
	Area Weightage 8%	317.84							
	Total	**4290.84**							
12	KSRB 7.9 : Providing and fixing M.S. grill work for windows and ventilators weighing 21 kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12 (P.32/I.7.9 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Kgs							
	W		10	1.50		1.20	18.00		
	V		10	1.50		0.45	6.75		
	GW		1	1.20		1.20	1.44		
	V2		2	1.20		0.45	1.08		

Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
		6	0.45		0.45	1.22		
		2	0.90		2.10	3.78		
Basic Rate	78.00	at 21 kgs /sqm				**32.27**		
Addl Area Weightage 8%	6.24					**677.57**		
Total	84.24				say	**677**	84.24	**57030.00**
Providing and fixing 12.5mm to 25 mm expanded metal work of 14 gauge with Mathi or Nandi wood patties of 50 mm x 12 mm size, including two coats approved paint etc., complete. (Including cost of screws). (P.265/I.37.54PW, P & MTD, SOUTH ZONE -SR 2016-17)	Sqm							
		10	1.50		1.20	18.00		
		10	1.50		0.45	6.75		
		1	1.20		1.20	1.44		
		2	1.20		0.45	1.08		
		6	0.45		0.45	1.22		
		2	0.90		2.10	3.78		
Basic Rate	1151.00					**32.27**	1243.08	**40108.00**
Addl Area Weightage 8%	92.08							
Total	1243.08							
KSRB 7.1: Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6mm with 08mm steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10cms. c to c applying a priming coat of red lead paint, cost of materials, labour, HOM of machinery complete as per specifications. size of gate 2.4m x1.4m Specification No. KBS 7.7/7.12 (P.31/I.7.1 PW, P & MTD, SOUTH ZONE -SR 2016-17)	Sqm							
		1	2.40		2.40	**5.76**	4355.64	**25088.00**
Basic Rate	4033.00							
Addl Area Weightage 8%	322.64							
Total	4355.64							

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
15	KSRB 7.5 : Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8 m. Specification No. KBS 7.10 / 7.12 (P.31/I.7.5 PW, P & IWTD,SOUTH ZONE -SR 2016-17)	Sqm							
	RS		1	3.00		2.50	**7.50**	3090.96	**23182.00**
	Basic Rate	2862.00							
	Area Weightage 8%	228.96							
	Total	**3090.96**							
16	KSRB 7.6: Providing and fixing top covers made out of 20 guage M.S. sheet over pull and push rolling shutters bent to shape including cost of red lead primer coat of painting, materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 7.10.6/7.12 (P.32/I.7.6 PW, P & IWTD,SOUTH ZONE -SR 2016-17)	Mtr							
	RS		1	3.00			**3.00**	510.84	**1533.00**
	Basic Rate	473.00							
	Area Weightage 8%	37.84							
	Total	**510.84**							
17	KSRB 15-3.5 : Providing 15mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P.113/I.15.13 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	Inside Plastering		2	18.00		3.30	118.80		
			2	8.00		3.30	52.80		
	Column Offsets		16	0.45		2.70	19.44		
	Staircase Portion		2	4.00		2.50	20.00		

Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
Toilet Rooms		2	2.00		2.50	10.00		
		20	1.20		3.00	72.00		
		4	1.80		3.00	21.60		
		2	2.60		3.00	15.60		
		2	3.70		3.00	22.20		
RO Plant		2	3.20		3.00	19.20		
		2	4.50		3.00	27.00		
		2	3.00		3.00	18.00		
Deduction						**416.64**		
MD	0.50	1	2.00		2.10	2.10		
D	0.50	2	1.20		2.10	2.52		
W	0.50	10	1.50		1.20	9.00		
V	0.50	10	1.50		0.45	3.38		
D	1.00	6	0.75		2.10	9.45		
GW	0.50	1	1.20		1.20	0.72		
V	0.50	2	1.20		0.45	0.54		
W1	0.50	6	0.45		0.45	0.61		
GD	0.50	2	0.90		2.10	1.89		
Open	1.00	1	1.00		2.60	2.60		
RS	0.50	1	3.04		2.50	3.80		
						36.60		
Basic Rate	186.00					**380.04**	200.88	**76342.00**
Add Area Weightage 8%	14.88							
Total	200.88							
KSRB15-3-13: Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications (P.114/I.15.21 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
Ceiling Plastering								
Hall		1	18.00	8.00		144.00		
Portico		1	4.00	3.00		12.00		
Beam Sides		6	8.00		0.60	28.80		
		2	4.00		0.45	3.60		
		4	3.00		0.45	5.40		
Staircase -W/S		1	2.50	1.00		2.50		
		1	1.50	1.00		1.50		
LS		1	2.00	1.20		2.40		
Steps		15	1.00		0.15	2.25		
Sides		2	2.50		0.15	0.75		
		2	1.50		0.15	0.45		
		2	2.00		0.15	0.60		
		2	1.20		0.15	0.36		
Toilet Rooms -Ladies Toilet		1	2.60	1.80		4.68		
WC		2	1.20	1.20		2.88		
Gents Toilet		1	3.70	1.80		6.66		
WC &Ticket Counter		3	1.20	1.20		4.32		
Store Room		1	1.80	1.20		2.16		
		1	1.00	1.35		1.35		
RO Plant		1	4.50	3.00		13.50		
		1	4.80	0.70		3.36		
Roof Beams		4	0.60	0.30		0.72		
Basic Rate	193.00					**244.24**	208.44	**50909.00**
Add Area Weightage 8%	15.44							
Total	208.44							

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
39	KSRB15-7: Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications (P.115/I.15.33 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
			Qty Vide Item No.37 + 38				**624.28**		
	Deduction wall tiles								
	For Gents & Ladies Toilets		20	1.20		2.10	50.40		
			4	1.80		2.10	15.12		
			2	2.60		2.10	10.92		
			2	3.70		2.10	15.54		
			2	3.20		2.10	13.44		
	Hall		2	18.00		1.20	43.20		
			2	8.00		1.20	19.20		
	RO Plant		2	4.50		2.10	18.90		
			2	3.00		2.10	12.60		
							199.32		
	Basic Rate	25.00					**424.96**	27.00	**11474.00**
	Add Area Weightage 8%	2.00							
	Total	27.00							
40	KSRB 15-3.6 : Providing 15mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P.113/I.15.14 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	Outside Plastering		2	18.30		3.45	126.27		
			2	8.30		3.45	57.27		
	Stair Case Head Room		2	4.00		2.10	16.80		
			2	2.00		2.10	8.40		
	Column Offsets		2	1.80		2.10	7.56		
	Chajja-W		2	18.30		0.60	21.96		
	Shelves		2	8.30		0.60	9.96		
	Drop Chajja		2	10.00		0.60	12.00		
	Toilet Rooms		2	8.10		3.15	51.03		
			2	3.50		3.15	22.05		
	RO Plant		2	4.80		3.15	30.24		
			2	3.30		3.15	20.79		
	Parapet		4	4.80		0.40	7.68		
			4	3.30		0.40	5.28		
			4	18.30		0.60	43.92		
			4	8.00		0.60	19.20		
			4	8.10		0.60	19.44		
			4	3.50		0.60	8.40		
							488.25		
	Deduction								
	MD	0.50	1	2.00		2.10	2.10		
	D	0.50	2	1.20		2.10	2.52		
	W	0.50	10	1.50		1.20	9.00		
	V	0.50	10	1.50		0.45	3.38		
	SW	0.50	1	1.20		1.20	0.72		
	V	0.50	2	1.20		0.45	0.54		

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
	V1	0.50	6	0.45		0.45	0.61		
	GD	0.50	2	0.90		2.10	1.89		
	RS	0.50	1	3.04		2.50	3.80		
	Basic Rate	167.00					**24.55**		
	Add Area Weightage 8%	13.36					**463.70**	180.36	**83632.00**
	Total	180.36							
47	Providing and fixing granite flooring in combination of 19mm thick (Avg) gang saw water cut LAKARED granite with 86% and with 14% of 19mm thick (avg.) Black granite in CM 1:4 proportion with a coat of rough plastering using CM 1:4, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing etc., complete including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification. (P.109/I.14.58 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	Flooring Portion								
	Hall		1	18.00	8.00		144.00		
	Portico		1	4.00	3.00		12.00		
	Skirting		2	15.00		1.20	36.00		
			2	8.00		1.20	19.20		
	LIS		1	2.00	1.20		2.40		
	Steps		15	1.00		0.45	6.75		
	Sides		15	0.45		0.15	1.01		
			1	2.00		0.15	0.30		
			2	1.20		0.15	0.36		
	RO Plant		1	4.50	3.00		13.50		
	Basic Rate	3722.00					**235.52**	4019.76	**946734.00**
	Add Area Weightage 8%	297.76							
	Total	4019.76							
48	KSRB 14.14-6: Providing Ceramic tiles of size 30x30 cms of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing,complete as per specifications. Specification No. KBS(P.106 / I.14.36.2 PW,P & IWTD,SOUTHZONE-SR2016-17)	Sqm							
	Ladies Toilet		1	2.60	1.80		4.68		
	WC		2	1.20	1.20		2.88		
	Gents Toilet		1	3.70	1.80		6.66		
	WC &Ticket Counter		3	1.20	1.20		4.32		

Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
Store Room		1	1.80	1.20		2.16		
		1	1.00	1.35		1.35		
Basic Rate	1176.00					**22.05**	1270.08	**28005.00**
Add Area Weightage 8%	94.08							
Total	1270.08							
KSRB 14-17.2: Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.. Specification No. KBS 14.16, 14.17 Colour glazed tiles 30×60cms 6mm thick with border of size 30×10cms. (P.106/I.14.41.2 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
wall tiles Portion								
For Gents & Ladies Toilets		20	1.20		2.10	50.40		
		4	1.80		2.10	15.12		
		2	2.60		2.10	10.92		
		2	3.70		2.10	15.54		
		2	3.20		2.10	13.44		
RO Plant		2	4.50		2.10	18.90		
		2	3.00		2.10	12.60		
						105.42		
Deduction								
D	2.00	6	0.75		2.10	18.90		
GW	0.50	1	1.20		1.20	0.72		
GD	2.00	2	0.90		2.10	7.56		
Open	2.00	1	1.00		2.10	4.20		
RS	0.50	1	3.00		2.10	6.30		
						37.68		
						67.74	1602.72	**108568.00**
Basic Rate	1484.00							
Add Area Weightage 8%	118.72							
Total	1602.72							
Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mix finished with flush pointing using white cement, including cost of materials, including cutting, grinding the edge to half/full round wherever required, labour, curing complete as per specification. (P.109/I.14.62 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
	Front & Back Side		2	8.30	3.00		49.80		
	Left & Right side		2	25.00	3.00		150.00		
			1	4.80		0.60	2.88		
	Basic Rate	1085.00					**202.68**	1171.80	**237500.00**
	Add Area Weightage 8%	86.80							
	Total	1171.80							
45	KSRB 15-15.1: Providing and applying painting in two coats with plastic emulsion paint with primer of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer (P.117/I.15.51.2 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
			Qty Vide Item No 39				**424.96**	97.20	**41306.00**
	Basic Rate	90.00							
	Add Area Weightage 8%	7.20							
	Total	97.20							
46	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint with primer of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer (P.118/I.15.53.2 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
			Qty Vide Item No 40				**463.70**	90.72	**42067.00**
	Basic Rate	84.00							
	Add Area Weightage 8%	6.72							
	Total	90.72							
47	KSRB 15-1 8.1 : Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications. (P.121/I.15.73 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	MD	2.25	1	2.00		2.10	9.45		
	D	2.25	2	1.20		2.10	11.34		
	W	1.00	10	1.50		1.20	18.00		
	V	1.00	10	1.50		0.45	6.75		
	DG	2.25	1	2.40		2.40	12.96		
	GW	1.00	1	1.20		1.20	1.44		
	V	1.00	2	1.50		0.45	1.35		
	VT	1.00	6	0.45		0.45	1.22		
	GD	1.00	2	0.90		2.10	3.78		

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
	RS	2.25	1	3.00		2.50	16.88		
	Basic Rate	29.00					**83.16**	31.32	**2605.00**
	Add Area Weightage 8%	2.32							
	Total	31.32							
	KSRB 15-18.2: Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (P.121/I.15.74 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Sqm							
	MD	2.25	1	2.00		2.10	9.45		
	D	2.25	2	1.20		2.10	11.34		
	W	1.00	10	1.50		1.20	18.00		
	V	1.00	10	1.50		0.45	6.75		
	CS	2.25	1	2.40		2.40	12.96		
	SW	1.00	1	1.20		1.20	1.44		
	V	1.00	2	1.50		0.45	1.35		
	VT	1.00	6	0.45		0.45	1.22		
	SD	1.00	2	0.90		2.10	3.78		
	RS	2.25	1	3.00		2.50	16.88		
	Basic Rate	82.00					**83.16**	88.56	**7365.00**
	Add Area Weightage 8%	6.56							
	Total	88.56							
	WATER SUPPLY AND SANITARY WORKS								
	KSRB 11-5: Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I/M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.Specification No. KBS11(P.77/I.12.5PW,P&IWTD,SOUTH ZONE -SR 2016-17)	Pan							
	Toilet Rooms		2				**2**	5540.40	**11081.00**
	Basic Rate	5130.00							
	Add Area Weightage 8%	410.40							
	Total	5540.40							

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
50	KSRB 11-1: Providing and fixing white vitreous china clay, water closet Indian type (Squatting pan) of size 580mm with footrests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 (P.79 / I.12.1 PW, P & IWTD,SOUTH ZONE -SR 2016-17)	Pan							
			2				2	3786.48	**7573.00**
	Basic Rate	3506.00							
	Add Area Weightage 8%	280.48							
	Total	3786.48							
51	KSRB 11-11.5: Providing and fixing white vitreous china clay, flat back wash basin size 450 x 300mm with a single 15mm C.P brass pillar tap with0.1 / M.S brackets, 32mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 (P.81/I.12.27 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Unit							
	Toilet Rooms		6				6	2839.32	**17036.00**
	Basic Rate	2629.00							
	Add Area Weightage 8%	210.32							
	Total	2839.32							
52	KSRB 11-17.2: Providing and fixing C.P. brass towel rail 600mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P. brass screws including cost of materials, labour complete as per specifications (P.83/I.12.46 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Unit							
			6				6	766.80	**4601.00**
	Basic Rate	710.00							
	Add Area Weightage 8%	56.80							
	Total	766.80							

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
53	KSRB 11-15.2: Providing and fixing 450mm dia circular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications. (P.82/I.12.40 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Unit							
			6				6	935.28	5612.00
	Basic Rate	866.00							
	Add Area Weightage 8%	69.28							
	Total	935.28							
54	Providing 15cms x 10cms stoneware gully trap of approved quality and make fixing in CC 1:2:4 and plastering with CM 1:3 wherever necessary. (Rate includes cost of all materials, fixtures and lead). (P.88 / I.12.112.2 PW, P & IWTD,SOUTH ZONE -SR 2016-17)	Each							
			10				10	291.60	2916.00
	Basic Rate:	270.00							
	Area Weightage 8%	21.60							
	Total	291.60							
55	Providing and fixing 12.5cms x 7.5cms CI Nahani trap of approved make conforming to PSI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). (P.88/I.12.113.2 PW, P & IWTD,SOUTH ZONE -SR 2016-17)	Each							
			4				4	307.80	1231.00
	Basic Rate:	285.00							
	Area Weightage 8%	22.80							
	Total	307.80							
	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC pipes and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 15mm nominal CD pipes (P.88/I.13.86.3 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	M							
			15	6.00			90.00	270.00	24300.00
	Basic Rate	250.00							

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
	Add Area Weightage 8%	20.00							
	Total	270.00							
(2)	KSRB 13-6.2-2 : Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.2/13.3 (P.91/I.13.27 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Each							
	Basic Rate	160.00	15				15	172.80	2592.00
	Add Area Weightage 8%	12.80							
	Total	172.80							
(3)	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (Internal work exposed on wall) - 20mm nominal OD pipes (P.96/I.13.85.2 PW, P & IWTD,SOUTH ZONE -SR 2016-17)	M							
	For Pipeline Work		6	6.00			36.00	145.80	5249.00
	Basic Rate	135.00							
	Area Weightage 8%	10.80							
	Total	**145.80**							
(4)	KSRB 13-11.1: Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity). Specification No. KBS 13.22 (P.94/I.13.78 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Nos							
	Basic Rate	8467.00	2				2	9144.36	18289.00
	Add Area Weightage 8%	677.36							
	Total	9144.36							

Sl. No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
	KSRB 12-8.1 : Constructing brick masonry inspection chamber 600x600mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, CI cover withframe (light duty) 600x600mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete 1:2:4 mix 20mm and downsize granite metal, foundation concrete 1:5:10 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. (P.73/I.11.50.1 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	Nos							
	Basic Rate	8954.00	4				**4**	9670.32	**38681.00**
	Add Area Weightage 8%	716.32							
	Total	9670.32							
	KSRB 13-8.9 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 140mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No. KBS 13.2.15.2 / 13.9 (P.94/I.13.73.6 PW, P & IWTD, SOUTH ZONE -SR 2016-17)	M							
	For Sanitary Purpose		1	30.00			**30.00**	774.36	**23231.00**
	Basic Rate	717.00							
	Add Area Weightage 8%	57.36							
	Total	774.36							